



Schedule - 'B'

Bruhath Bengaluru Mahangara Palike, Dasarhalli Zone


Name of the Work : Maintenance of UGD in Ward No.12 Shettyhalli, Shettyhalli Sub

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted	
				In Figures (Rs)	In Words (Rs)
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches stacking the excavated soil clear for edges of excavation with lead upto 50 m. after breaking of clods Complete as per specifications.	Cum	1463.28	314.83	Rupees Three Hundred and Fourteen and Eighty three Paisa Only
2	Providing and laying in position to required level or slope 230mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges Complete as per specifications.	Rmtr	985	581.82	Rupees Five Hundred and Eighty One and Eighty Two Paisa Only
3	Constructing brick masonry circular type manhole 0.91 m internal dia at bottom 0.91m deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement foundation concrete 1:3:6 mix using 40mm and downsize granite metal and making necessary channel in cement concrete 1:2:4 mix with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diameter confirming IS:12592, total weight cover and frame to be not less than 182kg fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of machineries complete as per specifications.(Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid separately) Complete as per specifications.	Nos	42	15104	Rupees Fifteen Thousand One Hundred and Four and One Paisa Only


Signature of the Contractor


Executive Engineer
EXECUTIVE ENGINEER
Bruhat Bangalore Mahangara Palike
Dasarahalli Division, Bangalore-560005

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted	
				In Figures (Rs)	In Words
4	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m. including cost of all labour Complete as per specifications.	Cum	1463.28	79.76	Rupees Seven Nine and Seventy Six Paise Only
5	Providing 12mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required, smooth rendering, : Providing and removing scaffolding, including cost of materials, labour. Curing Complete as per specifications.	Cum	237.38	183.56	Rupees One Hundred Eighty Three and Fifty Six Paise Only
6	Providing and fixing of Manhole SFRC Rings and Covers as Per IS Heavy Duty to Suit The Existing Damaged Manhole and Removing Debris inside and Outside the Manhole With all Lead and Lift Charges Complete as per specifications.	Nos	35	1146.05	Rupees One Thousand and One Hundred Fourty Six and Five Paise Only
	Cleaning The Blockage of Indian Coal Set & Soil Pipes Putting Into Working Underground Stone Ware Pipe old Repair Man Hole as Considerd With all Lead & Lift , Complete as per specifications.1	Mtr	12000	52.50	Rupees Fifty Two and Fifty Paise Only



EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-560057